



## **Waterproofing Of Underground RCC Structure**

Region

Delhi (India)

Type

Underground Specialized RCC Integrated Structure

**Main Contractor** 

Ahluwalia Contracts (I) Ltd.

**Execution of the work** 

Renesco India Private Limited

**Construction Period** 

2017-2021

## **Project Description**

Pressure waterproofing system (Submaine system of waterproofing) has to be applied, using PVC membrane of 2.0 thick, underground **RCC** on the including underground structures tanks. formation of compartments using with the PVC waterbar/PVC tape and each compartment is fitted with five pcs of injection flanges for the purpose of grouting as second line of defence if any damage occurs in future due to any reason. the system will prevent entry of water into the structure from outside surroundings and will facilitate a bone dry structure inside against presssurised ground water condition.



## Scope of work

Supply and apply of following itmes for around 20,000 Sqm surface area of the structures

- PVC membrane 2.0 mm thick with signal layer
- Non-woven Polypropylene based Geotextile with minimum weight of 300g/m2.
- Waterbar 280mm wide with four anchors 30mm height to form compartments and seal construction joints
- PVC termination tape 220 mm wide to form compartments and seal construction joints
- P.E Sheet 300 micron sliding layer
- High strength XPS board 25mm thick for protection layer
- Injection flanges
- System installed as per DVS 2212 guidelines by trained and certified PVC welders.



